

Costing for: **Typical Flue Detail Costing**  
House type: House with 300mm I.D. Flue  
Customer ref. Chimney Height 6000mm  
Site  
Plot number

Costing ref: **300id-6m-offset-23D**  
Date: 02 December 2025  
By: SJ  
Price list: March 2025

Components	Product code	Qty	Prices each	Cost £
Throat lintel/gather unit 1000mm wide	300TL1000	1	119.12	119.12
300mm flue liner bend at 30 degrees	300B	2	54.96	109.92
300mm flue liner 230mm tall	300L230	21	29.99	629.79
Flue liner sealant 310ml	Dunseal	12	7.35	88.20
Micafil Vermiculite 100 Litre	MV100L	4	38.39	153.56
300mm straight 750mm pot red	300RST750R	1	244.92	244.92
Topguard birdguard cowl 350 id red	TG350R	1	170.57	170.57
Flue notice plate	Plate	1	8.50	8.50
310ml Skeleton Gun	Sealgun	1	7.04	7.04
Red polypropylene air brick 220mm x 72mm	REDG930	6	1.02	6.12
High impact styrene black cavity sleeve 218mm x 72mm	CSG935	7	5.53	38.71
Smoke pellet tube	Smoke	1	12.47	12.47

Cost ex-works *	<b>1588.92</b>
Delivery charge	<b>75.00</b>
Goods	<b>£ 1,663.92</b>
VAT @ 20%	<b>332.78</b>
<b>Total</b>	<b>£ 1,996.70</b>

All prices are ex-works, valid for 30 days and are subject to VAT.  
Charge for individually plotting multiple flue orders is £40 per plot.  
Free delivery for orders over £1,000 nett invoice value (ex-Vat) to UK mainland excluding the Highlands of Scotland (POA).  
All trading is subject to our standard conditions of sale (copy available).





#### Notes

This flue costing is based on information provided. Please have your architect check the costing to your drawings prior to ordering to ensure that it meets with your requirements. Please also check the pot/terminal style and colour.

For construction guidance refer to the flue illustration and the installation guide available on our website [www.dunbrikflues.co.uk](http://www.dunbrikflues.co.uk)

**The infill is based on a 475mm x 375mm void between the liners and masonry**

Please ensure that the flue and chimney are constructed in accordance with Building regulations part J



Notes

Chimney Height taken from FFL to underside of chimney pot.

Please have your architect check this typical flue illustration to your drawings to ensure it meets both your requirements and current building regulations.

ALL DIMENSIONS ARE SHOWN IN MILLIMETRES  
NOT TO SCALE

The checklist is based on Building Regulations ADJ Appendix A. with Dunbrik flue liner system data. The builder/installer should insert details of the actual fireplace opening sizes, actual ventilation installed and any variations to the usual data.

For	<b>Typical Flue Detail Costing</b>	Costing ref	<b>300id-6m-offset-23D</b>
Site at		Plot number	
System	<b>Dunbrik 300mm id A1 concrete flue liners</b>	House type	<b>House with 300mm I.D. Flue</b>
Date	<b>02 Dec 2025</b>	Customer ref.	<b>Chimney Height 6000mm</b>

### Checklist for hearths, fireplaces, flues and chimneys

This checklist can help you to ensure hearths, fireplaces, flues and chimneys are satisfactory. If you have been directly engaged, copies should also be offered to the client and to the Building Control body to show what you have done to comply with the requirements of part J. If you are a sub-contractor, a copy should be offered to the main contractor.

Items listed in ADJ Appendix A		Details for builder to complete or amend
1 Building address, where work has been carried out		
		Amend
2 Identification of hearth, fireplace, chimney or flue.		<b>Fireplace in lounge</b>
3 Firing capability: solid fuel/gas/oil/all		<b>All</b>
4 Intended type of appliance. State type or make. If open fire give finished fireplace opening dimensions.		<b>For gas fire or solid fuel fire 471,200 sq.mm maximum</b>
5 Ventilation provisions for the appliance State type and area of permanently open air vents		<b>Through wall ventilation 35,300 sq mm minimum</b>
6 Chimney or flue construction a) State the type or make and whether new or existing. b) Internal flue size (and equivalent flue height, where calculated natural draught gas appliances only). c) If liners are used confirm they are correctly jointed in accordance with manufacturers instructions and state jointing materials used. d) If an existing chimney has been refurbished with a new liner, type or make of liner fitted. e) Details of flue outlet terminal f) Number and angle of bends. g) Provision for cleaning and recommended frequency.	Outlet detail Complies with:	<b>New masonry chimney with: Dunbrik A1 concrete flue liners to BSEN1857 300mm internal diameter  Tongue downwards into rebate and joined with Dunseal fireproof mortar  300mm straight 750mm pot BSEN13502:2002 2 bends ref 300B at 22.5 degrees  Annually via fireplace opening</b>
7 Hearth. Form of construction. New or existing		<b>New As diagram 25 in ADJ</b>
8 Inspection and testing after completion Test (Appendix E in AD J 2002) and results Flue inspection results Appliance (where included)	Visual Sweeping Coring ball Smoke Spillage	Tests carried out by:

**I/We the undersigned confirm that the above details are correct. In my opinion, these works comply with the relevant requirements in Part J of Schedule 1 to the Building Regulations.**

Print name & title	_____	Profession	_____
Capacity	_____	Tel no	_____
Address	_____	Postcode	_____
Signed	_____	Date	_____
Registered membership of (e.g. Gas Safety, OFTEC, HETAS, NACE, NACS)			